

Village of Glen Ellyn

Construction Rules of Conduct

- **Work Hours are 7:00 a.m. - 7:00 p.m. Monday - Saturday, 8:00 a.m. - 5:00 p.m. on Sunday.**
- **Properly install and maintain erosion control (silt fencing) according to construction plan or best management practices.**
- **Properly install and maintain tree protection fencing according to Tree Preservation Plan.**
- **Properly install and maintain perimeter site fencing and secure the site at the end of each working day.**
- **Provide and maintain a gravel access drive prior to construction above the foundation.**
- **Protect and maintain downgrade stormwater inlets with hay bales or filter fabric.**
- **Locate portable toilets out of public view or at least 10 feet from any lot line with the door facing your building.**
- **Stockpile equipment and materials a minimum of 10% of the lot width away from neighboring properties.**
- **Control weeds by trimming unsightly overgrowth regularly.**
- **Pick up scattered construction debris on a daily basis.**
- **If “tracking” occurs, clean the street at the end of each working day.**
- **Maintain emergency vehicle access on and around the site.**
- **Keep the pedestrian right-of-way maintained and free of construction materials and vehicles.**
- **Earth stockpiles must have erosion control if they are to remain for more than 3 days.**
- **A dumpster must be in place when appropriate for proper daily clean-up.**
- **Water pumped or otherwise discharged from the site shall be filtered.**
- **Stripped areas shall be permanently or temporarily protected from soil erosion within 15 days after final grade.**
- **When cutting masonry, brick or stone, dust control measures must be implemented.**
- **During demolition, dust and airborne particle control measures must be implemented.**
- **No open fires or burning. Contained fire for heating sand is allowed.**